



When Mico Industries wanted to relocate equipment from existing plants into a new facility, our turn-key solutions proved to be an advantage for getting the work done in a timely manner.



Industry: Heavy Industry

LOCATIONS:

- Grand Rapids, MI
- Wyoming, MI
- Kentwood, MI
- Battle Creek, MI

DEPARTMENTS INVOLVED:

- Electrical
- Fabrication
- Foundations
- Maintenance & Repair
- Rigging
- Trucking

SCOPE OF WORK:

Lee Contracting relocated three complete facilities into one new location. We upgraded the building's utility infrastructure to be able to support the new equipment. Our teams worked to load, transport, offload, stack and anchor an 1000T Bliss press, disconnect all interconnections (air, cooling, and hydraulic) at old facilities and reconnect the interconnections at the new facility.

CHALLENGES ENCOUNTERED:

The ABB machines were to be removed in one piece. We had to enlarge the doorway to complete this work. We had to cut the concrete wall, remove the slab, install a temporary wall and remove the siding. Once the machines were removed, we replaced the wall and reinstalled the siding.